



**MEGHALAYA ENERGY CORPORATION IMI**  
**OFFICE OF THE ADDITIONAL CHIEF ENGINEER (EL)**  
**MATERIAL MANAGEMENT**  
**LUM JINGSHAI; SHORT ROUND ROAD; SHILLONG-793001**

*Phone – 0364-2591930 E-mail: ace.mm.meecl@gmail.com Fax- 0364- 2590955*

**Purchase, Estimate & Issue rate of 132KV, 33KV & 11KV Isolators.**

SI No.	Item Description	Unit	Purchase Rate (₹)	Estimate rate inclusive of ED, CST & F&I. (₹)
1	145KV, 800A, HCB Normal Isolator with Motor operated Main switch and 1 no manually operated Earth switch & complete with terminal connectors suitable for ACSR Panther Conductor, & 145 KV Solid Core Post Insulators of 127 PCD bending Strength 4KN with a total height of 1500 mm of reputed Make and Galvanised angles Mounting Structures.	No	382003.55	401103.73
2	Same as above without Earth Switch.	No	351443.33	369015.50
3	33KV, 630A, (manually Operated ) Isolator with Earth Blade/ Switch as per IS. G. Nandy & Co. make.	No	49047.38	49047.38
4	33KV, 630A, (manually Operated ) Isolator without Earth Blade/ Switch as per IS. G. Nandy & Co. make.	No	33690.02	33690.02
5	33KV Solid core Post Insulators ( 9 nos/set) MIL/BirlaNGK as per IS.	No	22115.81	22115.81
6	Mounting Structure for above	No	18620.29	18620.29
7	Al. Terminal connectors 6 nos/ set, rigid type for ACSR Wolf Conductor	No	2216.58	2216.58
8	33KV, 400A, (manually Operated ) Isolator with Earth Blade/ Switch as per IS Power Line Accessories make	No	49047.38	49047.38
9	33KV, 400A, (manually Operated ) Isolator without Earth Blade/ Switch as per IS. Power Line Accessories make	No	33690.02	33690.02
10	33KV Solid core Post Insulators ( 9 nos/set) MIL/BirlaNGK as per IS.	No	22115.81	22115.81
11	Mounting Structure for above	No	18620.29	18620.29
12	Al. Terminal connectors 6 nos/ set, rigid type for ACSR Wolf Conductor	No	2216.58	2216.58
13	11KV, 400Amp Isolator with Earth blade along with insulators, Galvanised foundation bolts, terminal connectors.	No	38800.00	41430.50
14	33KV, 630A, (manually Operated ) Isolator with Earth Blade/ Switch complete set. Including SI no 5, 6 & 7.	Set	92000.06	92000.06
15	33KV, 630A, (manually Operated ) Isolator without Earth Blade/ Switch complete set. Including SI no 5, 6 & 7.	Set	76642.70	76642.70
16	33KV, 400A, (manually Operated ) Isolator with Earth Blade/ Switch complete set.	Set	92000.06	92000.06

17	33KV, 400A, (manually Operated ) Isolator without Earth Blade/ Switch complete set. Including SI no 10, 11 & 12.	Set	76642.70	76642.70
----	--	-----	----------	----------

# FED

<b>Issue Rate (Estimate rate + Storage &amp; handling Charges @7.5%) (₹)</b>
431186.51
396691.66
52725.93
36216.77
23774.50
20016.81
2382.82
52725.93
36216.77
23774.50
20016.81
2382.82
44537.79
98900.06
82390.90
98900.06

82390.90