

Price Bid for Overhauling of 20 MVA Transformer No-III at 132KV Mawlai Grid Sub-Station.

A) Service Price Schedule:

Sl. No	Description of the Job	Quantity	Unit	Unit Price (in Rs)	Total Price (in Rs)
1	Dismantling charges of all accessories of 20 MVA	1	NO		
2	Overhauling & cleaning of Main Tank, Change of Gaskets, Re-Assembly of Active Part & Installation charges of 20MVA Transformer, Crane charges include	1	NO		
3	Oil Filtration & Drying out process (15/20 cycles with N2 Gas) will be done by Operator. Oil Filtration Machine and Storage Tank shall be supplied by MePTCL, free of cost. Our cost is inclusive of To & Fro Transportation cost of filter Machine & Storage Tank. Nitrogen Gas Cylinders shall be supplied by us on Returnable basis.	1	NO		
TOTAL (A)					

B) Material Price Schedule:

Sl. No	Description of the Job	Quantity	Unit	Unit Price (in Rs)	Total Price (in Rs)
1	Transformer Oil	10450 (50 Drums)	Ltr		
2	Rubberized Cork Sheet, size: 900 x 600 x 12mm thick.	8	NO		
3	Rubberized Cork Sheet, size: 900 x 600 x 8mm thick.	4	NO		
4	Nitrogen Gas Cylinder for Vacuum of 15/20 cycles (Cylinder will be supplied on Returnable basis).	40	NO		
TOTAL (B)					

C) Testing Charge :

Sl. No	Description of the Job	Quantity	Unit	Unit Price (in Rs)	Total Price (in Rs)
1	Pre- Commissioning Testing of 20MVA Transformer	1	NO		
2	SFRA Testing	2	NO		
TOTAL (C)					

TOTAL (A + B + C) : Rs				
-------------------------------	--	--	--	--

|