

**PRICE BID FOR P.C.C OF 132 KV & 33 KV SWITCHYARD AT 132/33 KV 2X20 MVA LAD  
NONGKREM(MAWLNDEP) SUB-STATION**

*(Rate should be inclusive of GST)*

Area of the Switch yard= 3609 - Area of Transformers - 132KV Columns - Terminal equipments -Cable Trench  
= 3609- 56.00 - 91.00 - 33.00 - 350= 3079 M<sup>2</sup>

<b>Sl.No</b>	<b>Description of works</b>	<b>Unit</b>	<b>Qty</b>	<b>Rate (Rs)</b>	<b>Amount (Rs)</b>
1	Earth work in excavation in foundation trenches including dressing of sides ramming of including stacking of serviceable stones , disposal and removal of excavated earth within a lead of 50m and lift of 1.50m complete as directed. a) in ordinary soil . 3079x0.30 = 923.70 m <sup>3</sup>	m <sup>3</sup>	923.70		
2	Providing brick soling in foundation and used floor with stone/best quality picked jhama brick,sand packed and laid to level and in panel after preparing the subgrade as directed including all labour and materials and if necessary dewatering,complete. ( c ) Stone soling of thickness 100mm = 3079 m <sup>2</sup>	m <sup>2</sup>	3079.00		
3	Plain cement concrete works with coarse aggregate of sizes 13mm to 32mm in foundtion bed for footing steps,walls,brick works etc as directed and specified including dewatering if necessary and curing complete(shuttering where necessart shall be measured and paid separately) (a) in prop 1:4:8 (1 cement:4 coarse sand:8 coarse agg. by volume(using mixture machine). 3079x0.10 = 307.90 m <sup>3</sup>	m <sup>3</sup>	307.90		
4	10mm thick cement plaster in single cot on fair side of brick/concrete walls for interior plastering up to 1st floor level including arises or rounded angles not exceeding 80mm girth and finished even and smooth including curing complete as directed . a) In cement mortar 1:3 =3079 m <sup>2</sup>	m <sup>2</sup>	3079.00		
	<b>TOTAL</b>				

