

PRICE BID FOR CONSTRUCTION OF PARKING AREA AT LAD NONGKREM(MAWLYNDEP) SUBSTATION					
<u>Item No.</u>	<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Rate in Rs. (inclusive of GST)</u>	<u>Amount in Rs.</u>
1	Earthwork in excavation upto a depth of 2m below the existing ground level for foundation trenches of foundations, footings of column/walls, retaining walls, septic tank etc. including bailing out water where necessary and removal of surplus earth with all lead and lifts as directed and specified for the following classification of soils.				
	In hard/ dense soil	201.000	m ³		
2	Filling floor with broken bricks bats/stone aggregates and sand including compacting and supplying of materials complete as specified and directed for levels.				
	Stone aggregates, initial 100mm,final	150.750	m ³		
3	Plain cement concrete works with coarse aggregate of sizes 13mm to 32mm in foundation bed for footing steps, walls, brick works etc. as directed and specified including dewatering if necessary, and curing complete (shuttering where necessary shall be measured and paid separately).				
	In Foundations and sub-structure including footing, columns with base, tie beam and plinth beams, pile cap, raft slab, base slab, RCC walls, retaining walls, walls of septic tank, inspection pit and the like and other works not less than 100mm thick up to plinth level.				
	(Without using admixture, plasticiser)				
	in prop 1:3:6(1 cement : 3 coarse sand : 6 coarse aggregate)	150.750	m ³		
4	Extra for carriage				
	(i) Stone solling/aggregate (Annexure-B)	7896.290	km-m ³		
	Total distance for Mawphlang to Mawlyndep= (45-8) = 27 Km				
	(ii) Sand from Kynshi to Mawlyndep (Annexure-C-14.1)				
	Total Distance = (75-15) = 67 Km	4747.120	km-m ³		
	TOTAL (Price inclusive of all taxes)				

(Rupees)

Name & Signature of the Bidder: