

**PRICE BID FOR SPREADING OF STONE CHIPS AT THE SWITCHYARD AREA OF 132/33KV,2X20 MVA LAD  
NONGKREM(MAWLYNDEP) SUBSTATION**

**Area of the Switchyard= 3609 - Area of Transformer - 132KV Column- Terminal equipments - Cable Trench=3609-56.00-  
91.00-33.00-350=3079M<sup>2</sup>**

<u>Item No.</u>	<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Rate in Rs. (inclusive of GST)</u>	<u>Amount in Rs.</u>
1	Supply of Gravel/stone aggregate two layers of 50mm (Total 100mm thick) with 10mm ungraded nominal size stone aggregate/pebles in switchyard area as per technical specification. (Rate as per SOR of MPWD (B) 2013-14 page 117, Sl.No. 5: Excluding labor cost for spreading). There is no rate for the same item in PWD (B) SOR 2015-16 3079x0.15=461.85m <sup>3</sup>	461.850	m <sup>3</sup>		
2	Spreading, Filling of Gravel in the switchyard, two layers of 50mm (Total 100mm thick) with 10mm ungraded nominal size stone aggregate/pebles as per technical specification. (Rate is taken as 10% of cost of Gravel) (Rate from Page- 34) 3079x0.15=461.85m <sup>3</sup>	461.850	m <sup>3</sup>		
3	Quantity from Sl.No. 1 above. The work involves head loading as well, the rate is taken 20% of Sl.No. 1 above.	17088.450	km- m <sup>3</sup>		
	Extra lead per km truck carriage for sand, gravel, Mawthup beyond the initial lead of 8 km				
	(i) Stone and Aggregate (As per annexure -C)				
	From Lad Mawphlang to Shillong-Mawlyndep, 45km=45-8=37km extra lead				
	37x461.85=17088.45				
	Total				

Name & Signature of the Contractor: