

BID SHEET FOR RENOVATION OF THE EXISTING BOUNDARY FENCING AT 132 KV EPIP-I SUBSTATION MePTCL RAJABHAGAN,BYRNIHAT.					
Items No.	Description	Qty	Unt	Rate (Rs.)	Amount (Rs.)
1	Providing brick nogged wall with first class brick in cement mortar etc	168.00	sqm		
2	Providing 12mm thick cement plaster including cleaning the surface and curing complete as directed.	336.00	sqm		
3	White washing				
	White washing with lime on wall surfaces (two coats) to give an even shade including thoroughly brooming the surface to remove all dirt, dust, mortar drops and other foreign matter.	672.00	sqm		
4	BARBED WIRE FENCING				
	Providing barbed wire on the existing barbed wire fencing with seven strands of barbed wire 12 S.W. G.x 2pliesx 4 points at 75mm apart including supplying, fitting and fixing with galvanised staples 38mmx38mmx3mm sizes with existing posts of the fencing , including removing rotten barbed wire as directed, complete with strengthening of post and tightening of the old barbed wire and joining old serviceable pieces on remaining lines as and where necessary and as directed.-	560	R.M		
5	Supplying, fitting and fixing galvanised barbed wire fencing with seven strands of barbed wire 12 S. W. G .x 2plies x 4 points at 75mm apart with angle iron intermediate fencing posts not more than 1800mm apart and straining corner and end post etc. as necessary to be fitted with straining eye bolts and staples etc. complete as directed, specification of the angle iron post as given below. (b) Straining post 65mm x 65mm x 6mm x1820mm	48.00	R.M		
TOTAL					

()

Signature of the Contractor