

BID SHEET FOR REPAIRING THE ROOF COVERING OF THE CONTROL ROOM CUM OFFICE AT 132KV GRID SUBSTATION MePTCL SOHRA					
SL. NO	DESCRIPTION	Quantity	Unit	Rate	Amount inclusive of GST(Rs)
1	Dismantling all types of corrugated/Trapezoidal sheet roofing including ridges, hips valleys and gutters etc. and stacking the materials as directed by the department at all levels.	226.02	Sqm		
	Roof				
	Varendah				
2	Providing Pre Painted Galvanized Iron Sheet Roofing (PPGI) (Dyna roof /Sathyam/ Durakolor/ Century Wells/Prestar/Wonder Roof make or equivalent) at all levels including supplying, fitting and fixing with self drilling, self tapping screws complete (Roof trusses, purlins etc. to be measured and paid separately.).	226.02	Sqm		
	0.60 mm thick				
	Roof				
	Varendah				
3	Providing Pre Painted Galvalume Sheet Roofing (PPGL) accessories like Ridges/Valle/Gutter/Flashing (Dyna roof/ Sathyam/DuraKolor/Century Wells/Prestar/ Wonder Roof/ make or equivalent) at all levels including fitting and fixing self drilling, self tapping screws complete.	31.33	Sqm		
	0.60 mm thick				
4	Steel workwelded in built up sections, framed work including cutting, hoisting and fixing in positions and applying priming coat fixing with bolts and nuts or welding, if necessary as directed	25.0084	Qntl		
	In trusses and trussed purlins upto 25 m span and 15 m overall height				
	60x60x4mm Roof				
	60x60x4mm Varendahfront				
	60x60x4mm Varendah front				
TOTAL =					

(Rupees

) only

Signature of the contractor with seal