BID SHEET FOR CONSTRUCTION OF PARKING IN FRONT OF FIELD HOSTEL AT 132/33KV MAWLYNDEP GRID SUBSTATION LAD NONGKREM					
Item No.	**Description**	**Quantity**	**Unit**	**Rate in Rs.**	**Amount in Rs.**
1	Earthwork in excavation upto a depth of 2m below the existing ground level for foundation trenches of foundations, footings of column/walls, retaining walls, septic tank etc. including bailing out water where necessary and removal of surplus earth with all lead and lifts as directed and specified for the following classificaiton of soils.	114.02	m^3		
	Retaining wall				
2	Filling sunken floor with broken brick bats/ stone aggregatesand sand including compacting and supplying of materials complete as specified and directed for all levels.	49.61	m^3		
	Stone aggregates,				
3	Plain cement concrete works in foundation bed for footingsteps, walls, brick works etc below plinth level as directedand specified including dewatering if necessary, and curingcomplete (shuttering where necessary shall be measured and paid separately).	28.74	m^3		
	Retaining wall				
4	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1cement: 6 coarse sand: 12 graded stone aggregate 20 mm nominal size) up to plinth level with:	21.220	m^3		
	Cement mortar 1 :6 (1 cement: 6 coarse sand)				
	Retaining wall				
5	CEMENT PLASTER(IN FINE SAND)	88.380	m^3		
	(Rupees)				

Signature of the Contractor