



MEGHALAYA ENERGY CORPORATION LIMITED

OFFICE OF THE ADDITIONAL CHIEF ENGINEER (EL)

MATERIAL MANAGEMENT

LUM JINGSHAI; SHORT ROUND ROAD; SHILLONG-793001

CIN: U40101ML2009GC008374

Phone – 0364-2591930

✉: ace.mm.meecl@meghalaya.gov.in

No. MeECL/ACE(MM)/Major-Items/Rfq/2026-27/06

Dated: 26th October 2026

CORRIGENDUM

Sub: Corrigendum to the Request for Quotation (RFQ) for Procurement of Major Items on Quarterly Requirement Basis – Amendment of Specifications and Extension of Submission Deadline.

Ref: No. MeECL/ACE(MM)/Major-Items/Rfq/-/2026-27/01 dated 14th October 2026

In response to requests received from participating bidders, the specifications of the items covered under the RFQ have been reviewed and amended. The revised specifications are enclosed as Annexure-I to this Corrigendum and shall supersede the corresponding specifications specified earlier in the RFQ.

- 1. The last date and time for submission of quotations are hereby extended up to 30.10.2026 at 3:00 P.M.**
- 2. Opening of Quotations: The quotations shall be opened on 30.10.2026 at 3:30 P.M in the Conference Room, MeECL, Lumjingshai.**

All other terms and conditions of the original RFQ, including the approved procurement methodology and the applicable Terms and Conditions for Registered Suppliers, shall remain unchanged and continue to apply.

All eligible registered suppliers are requested to take note of the above amendments and submit their quotations accordingly.

This corrigendum shall form an integral part of the original RFQ.

Additional Chief Engineer (MM)

MeECL, Lum Jingshai, Shillong

For and on behalf of MeECL / MePDCL / MePTCL / MePGCL

Memo. No MeECL/ACE(MM)/Major-Items/Rfq/_/2026-27/ 06(a)

Dated Shillong the 26th October 2026

Copy to:

1. PA to the Chairman-cum-Managing Director, MeECL for favour of information to the CMD.
2. The Director (Finance), MeECL, Shillong - for information with reference to Office Order dated 06.10.2026.
3. The Director (Distribution), MePDCL, Shillong.
4. The Director (Transmission), MePTCL, Shillong.
5. The Director (Generation), MePGCL, Shillong
6. The Company Secretary, MeECL, Shillong.
7. The Chief Engineer (Distribution), MePDCL, Shillong/Tura.
8. The Executive Engineer (MM Stores), MeECL Shillong - for information and necessary action.
9. The Executive Engineer (MIS & IT), MePDCL Shillong for uploading in the MeECL Website.
10. All Registered Suppliers, MeECL (Major Items) - Through Email / MeECL portal / Website.
11. Notice Board, O/o ACE(MM), MeECL/HQ
12. Office Copy

Additional Chief Engineer
Material Management



MEGHALAYA ENERGY CORPORATION LIMITED

OFFICE OF THE ADDITIONAL CHIEF ENGINEER (EL)

MATERIAL MANAGEMENT

LUM JINGSHAI; SHORT ROUND ROAD; SHILLONG-793001

CIN: U40101ML2009GC008374

Phone – 0364-2591930

E-mail: ace.mm.meecl@meghalaya.gov.in

ANNEXURE-1

ESTIMATE OF MATERIALS AS PER APPROVED O&M WORKS FOR THE 1ST QTR (EZ&WZ) FOR TENDERING PURPOSE

Sl No	Item Category	Particulars	HSN Code	Unit	Qty	For/Dest/Unit Rate Excl of GST	GST Amt	Amount
1	Cable 11KV	1-Core: 11KV(E) Al, XLPE, GI Strip, IS:7098-II						
		Stranded Compacted Circular Aluminum Conductor, Conductor Screen with Extruded Semi Conducting Compound, XLPE Insulated, Insulation Screening with Extruded Semi Conducting Compound in Combination with Copper Tape, Cores Laid Up, Inner sheath of PVC, Galvanised Steel Flat Strip Armoured, & Overall PVC Sheathed Cable Conforming to IS 7098-II						
1.1		Cable 11KV XLPE Armoured 1-CORE 120 SQMM		Mtr	200			
1.2		Cable 11KV XLPE Armoured 1-CORE 240 SQMM		Mtr	200			
1.3		Cable 11KV XLPE Armoured 1-CORE 300 SQMM		Mtr	200			
	Cable 11KV	3-Core, 11KV(E), Al, XLPE, GI Strip, PVC Sheath, IS:7098-II						
		Stranded Compacted Circular Aluminum Conductor, Conductor Screen with Extruded Semi Conducting Compound, XLPE Insulated, Insulation Screening with Extruded Semi Conducting Compound in Combination with Copper Tape, Cores Laid Up, Inner sheath of PVC, Galvanised Steel Flat Strip Armoured, & Overall PVC Sheathed Cable Conforming to IS 7098-II						
1.4		Cable 11KV XLPE Armoured 3-CORE 120 SQMM		Mtr	200			
1.5		Cable 11KV XLPE Armoured 3-CORE 185 SQMM		Mtr	200			
1.6		Cable 11KV XLPE Armoured 3-CORE 240 SQMM		Mtr	200			



MEGHALAYA ENERGY CORPORATION LIMITED

OFFICE OF THE ADDITIONAL CHIEF ENGINEER (EL)

MATERIAL MANAGEMENT

LUM JINGSHAI; SHORT ROUND ROAD; SHILLONG-793001

CIN: U40101ML2009GC008374

Phone – 0364-2591930

✉: ace.mm.meecl@meghalaya.gov.in

1.7		Cable 11KV XLPE Armoured 3-CORE 300 SQMM	Mtr	200			
1.8		Cable 11KV XLPE Armoured 3-CORE 95 SQMM	Mtr	200			
2	Control Cable	1.1KV, Cu, XLPE/PVC, Steel Wire Armoured, IS:7098/1554					
2.1		Control Cable Armoured 10-Core, 1.5 Sqmm	Mtr	200			
2.2		Control Cable Armoured 10-Core, 2.5 Sqmm	Mtr	200			
2.3		Control Cable Armoured 12-Core, 2.5 Sqmm	Mtr	200			
2.4		Control Cable Un-Armoured 10-Core, 1.5 Sqmm	Mtr	200			
2.5		Control Cable Unarmoured 10-Core, 2.5 Sqmm	Mtr	200			
2.6		Control Cable Unarmoured 4-Core, 2.5 Sqmm	Mtr	100			
2.7		Control Cable Unarmoured 6-Core, 2.5 Sqmm	Mtr	100			
3	Cable LT	1 Core: 1.1KV, Al, XLPE, Arm: GI Wire/Strip, IS:7098.					
3.1		Cable LT Armoured 1-Core 120 Sqmm	Mtr	300			
3.2		Cable LT Armoured 1-Core 150 Sqmm	Mtr	200			
3.3		Cable LT Armoured 1-Core 185 Sqmm	Mtr	200			
3.4		Cable LT Armoured 1-Core 240 Sqmm	Mtr	300			
3.5		Cable LT Armoured 1-Core 300 Sqmm	Mtr	200			
3.6		Cable LT Armoured 1-Core 35 Sqmm	Mtr	200			
3.7		Cable LT Armoured 1-Core 400 Sqmm	Mtr	200			
3.8		Cable LT Armoured 1-Core 50 Sqmm	Mtr	200			
3.9		Cable LT Armoured 1-Core, 70 Sqmm	Mtr	300			
3.10		Cable LT Armoured 1-Core, 95 Sqmm	Mtr	300			
3.11		Cable LT Un-Armoured 1-Core, 400 Sqmm	Mtr	200			
	Cable LT	3.5 Core: 1.1KV, Al, XLPE/PVC, Steel Strip Armoured, IS:7098					
3.12		Cable LT Armoured 3.5-Core, 120 Sqmm	Mtr	200			



MEGHALAYA ENERGY CORPORATION LIMITED

OFFICE OF THE ADDITIONAL CHIEF ENGINEER (EL)

MATERIAL MANAGEMENT

LUM JINGSHAI; SHORT ROUND ROAD; SHILLONG-793001

CIN: U40101ML2009GC008374

Phone – 0364-2591930

E-mail: ace.mm.meecl@meghalaya.gov.in

3.13		Cable LT Armoured 3.5-Core, 150 Sqmm	Mtr	200			
3.14		Cable LT Armoured 3.5-Core, 185 Sqmm	Mtr	200			
3.15		Cable LT Armoured 3.5-Core, 240 Sqmm	Mtr	200			
3.16		Cable LT Armoured 3.5-Core, 300 Sqmm	Mtr	200			
3.17		Cable LT Armoured 3.5-Core, 400 Sqmm	Mtr	200			
3.18		Cable LT Armoured 3.5-Core, 50 Sqmm	Mtr	200			
3.19		Cable LT Armoured 3.5-Core, 70 Sqmm	Mtr	200			
3.20		Cable LT Armoured 3.5-Core, 95 Sqmm	Mtr	200			
4	Cable LT AB	1.1KV, Al, XLPE Ins, With Messenger, IS:14255					
4.1		LT AB Cable (4C*35 Sqmm +1C*25 sqmm)	Mtr	500			
5	ACSR Conductor	IS:398 (Part-2) / IEC:61089 Construction: Al Wires 1350-H19 stranded over Galv. Steel Core					
5.1		ACSR Cond ACSR RABBIT	Km	5			
5.2		ACSR Cond ACSR RACOON	Km	15			
5.3		ACSR Cond ACSR SQUIRREL	Km	20			
5.4		ACSR Cond WEASEL	Km	50			
5.5		ACSR Cond WOLF	Km	5			
6	11KV CT-PT Set (3Phase-4Wire)	11KV CT-PT Set (3P-4W): 11KV/110V, 0.5S, 30VA, Outdoor Oil Type, SC 13.1KA/3 Sec, 12KV, IS:2705/3156 With Warranty of 36 Months (Minimum)			Manufacturer should submit Valid Type Test (BIS/ISO) Report of not less than 5 years		
6.1		CT-PT Comb Set 11KV 100-200/5A	No	2			
6.2		CT-PT Comb Set 11KV 10-15/5A	No	2			
6.3		CT-PT Comb Set 11KV 10-20/5A	No	5			
6.4		CT-PT Comb Set 11KV 20-40/5A	No	12			
6.5		CT-PT Comb Set 11KV 150-300/5A	No	5			
6.6		CT-PT Comb Set 11KV 15-25/5A	No	5			
6.7		CT-PT Comb Set 11KV 15-30/5A	No	5			
6.8		CT-PT Comb Set 11KV 200-400/5A	No	5			
6.9		CT-PT Comb Set 11KV 20-40/5A	No	6			
6.10		CT-PT Comb Set 11KV 25-50/5A	No	5			
6.11		CT-PT Comb Set 11KV 300-400/5A	No	5			
6.12		CT-PT Comb Set 11KV 30-50/5A	No	3			
6.13		CT-PT Comb Set 11KV 50-100/5A	No	3			



MEGHALAYA ENERGY CORPORATION LIMITED

OFFICE OF THE ADDITIONAL CHIEF ENGINEER (EL)

MATERIAL MANAGEMENT

LUM JINGSHAI; SHORT ROUND ROAD; SHILLONG-793001

CIN: U40101ML2009GC008374

Phone – 0364-2591930

E-mail: ace.mm.meecl@meghalaya.gov.in

6.14		CT-PT Comb Set 11KV 5-10/5A	No	3			
	33KV CT-PT Set (3Phase-4Wire)	33KV/110V, 0.5S Class, 30VA, Outdoor Oil Type, SC 26.24KA/3Sec (1500 MVA), 36/70/170KV, IS:2705/3156 With Warranty of 36 Months (Minimum)			Manufacturer should submit Valid Type Test (BIS/ISO) Report of not less than 5 years		
6.15		CT-PT Comb Set 33KV 100-200/5A	No	3			
6.16		CT-PT Comb Set 33KV 200-400/5A	No	3			
6.17		CT-PT Comb Set 33KV 300-600/5A	No	3			
6.18		CT-PT Comb Set 33KV 50-100/5A	No	6			
6.19		CT-PT Comb Set 33KV 5-10/5A	No	3			
6.20		CT-PT Comb Set 33KV/110V 100/5A	No	3			
6.21		CT-PT Comb Set 33KV/110V 150/5A	No	3			
6.22		CT-PT Comb Set 33KV/15-30/5A	No	3			
7	33KV Single Phase Current Transformer	33KV, 30VA, 0.5S, 26.24KA/3Sec, Outdoor, Oil, 36KV, IS:2705, Complete Set With Warranty of 36 Months (Minimum)			Manufacturer should submit Valid Type Test (BIS/ISO) Report of not less than 5 years		
7.1		C.T, 200-400/1/1A	No	3			
7.2		C.T, 200-400/5/5A	No	3			
7.3		C.T, 100-200/5/5A	No	2			
7.4		C.T, 50-100/5/5A	No	2			
8	Galvanised Pole	Steel Tabular Poles, GI, with Base Plate, IS:2713, IS:2629 Galvanised					
8.1		Poles G.I. SP-04/7.5 MTR	No	75			
8.2		Poles G.I. SP-14/8 MTR	No	150			
8.3		Poles G.I. SP-39/9.5 MTR	No	25			
8.4		Poles G.I. SP-60/12 MTR-N/D	No	25			
8.5		Poles G.I.SP-66/12 MTR-H/D	No	25			
8.6		Poles G.I.SP-76/14.5 MTR-H/D	No	20			
9.0	Insulator	11KV: Porcelain/, 255mm Dia, 145mm Spacing, 320mm CD					
		33KV: Porcelain/, 255mm Dia, 145mm Spacing, 960mm CD					
		Std: IS:731					
9.1		Disc Insulator 90 KN (Normal)	No	150			
9.2		Insulator DISC, 45KN/11KV	No	250			
9.3		Insulator DISC.70KN/33KV	No	100			
9.4		Insulator Pin LT	No	500			
9.5		Insulator Pin.11KV/5KN	No	750			
9.6		Insulator PIN.33KV/10KN	No	250			



MEGHALAYA ENERGY CORPORATION LIMITED

OFFICE OF THE ADDITIONAL CHIEF ENGINEER (EL)

MATERIAL MANAGEMENT

LUM JINGSHAI; SHORT ROUND ROAD; SHILLONG-793001

CIN: U40101ML2009GC008374

Phone – 0364-2591930

E: ace.mm.meecl@meghalaya.gov.in

	Insulator (Polymer)	11KV: Poly Tension Insulator (T&C), Polymer, 45kN, 320mm Creepage with N/B, Weight Approx-1.2 Kg						
		33KV: Poly Tension Insulator (T&C), Polymer, 70kN/90KN, 350mm Creepage with N/B, Weight Approx-1.7/2.2 Kg						
		Std: IEC 61109 / IS 731						
9.1a		33KV/90KN Tension Insulator with Clamp & N/B		No	100			
9.2a		33KV/70KN Tension Insulator with Clamp & N/B		No	100			
9.3a		11KV/45KN Tension Insulator with Clamp & N/B		No	200			
9.4a		11KV Pin Insulator with GI & N/B		No	500			
9.5a		33KV Pin Insulator with GI & N/B		No	200			
10	Lightning Arrester	11KV: 9KV Rating, 12KV MCOV, 10KA, Class-2, ZnO, IS:3070						
		33KV: 30KV Rating, 24KV MCOV, 10KA, Class-2/3, ZnO, Polymer, IS:3070						
10.1		Lightning Arrester 11 KV		No	150			
10.2		Lightning Arrester 33 KV		No	100			
11	Smart Meter	1Ph/3Ph, 5-30A / 10-60A, 240V/415V, Class 1.0, DLMS/4G/ TOD/Net Metering, IS:16444						
11.1		Energy Meter Smart LT Static 1PH 2W		No	500			
11.2		Energy Meter Smart 3 Phase		No	100			
11.3		Energy Meter Static CT-PT Op Smart 3P-4W		No	50			
11.4		Energy Meter Smart LT-CT, 3P4W 3*240/5A_1		No	50			
12	Meter Box	1Ph/3Ph, PC/ABS, IP54, UV Stabilized, 1mm Thick, Transparent Window, for 1 Meter, IS:14772						
12.1		Meter Box For 1PH 2W Smart METER		No	500			
12.2		Meter Box for 3PH Smart METER		No	100			
12.3		Meter Box for Instrument X-Mer HT Energy METER		No	50			
12.4		Meter Box LT Static Meter Sintex (Pilfer PROOF)		No	50			



MEGHALAYA ENERGY CORPORATION LIMITED

OFFICE OF THE ADDITIONAL CHIEF ENGINEER (EL)

MATERIAL MANAGEMENT

LUM JINGSHAI; SHORT ROUND ROAD; SHILLONG-793001

CIN: U40101ML2009GC008374

Phone – 0364-2591930

E: ace.mm.meecl@meghalaya.gov.in

13	Potential Transformer	33KV/ $\sqrt{3}$ / 110V/ $\sqrt{3}$, 30VA, 0.5 Class, 36KV Max, 70KV/170KVp, Oil Filled, Outdoor, IS:3156 With Warranty of 36 Months (Minimum)						
13.1		33KV PT outdoor type oil filled, 33KV/ $\sqrt{3}$ /110V/ $\sqrt{3}$, class- 0.2s, 3P, 30VA.		No	6			
14	Transformer Oil	IS:335 / IEC:60296 Type: Mineral Insulating Oil, Uninhibited / Inhibited						
14.1		Transformer Oil		Ltr	12540			
15	VCB	36KV, 1250/1600A, 25/31.5KA, 3 Ph, Outdoor, Spring Charge, 110V DC, IS:13134						
15.1		VCB Circuit Breaker 3PH-33KV-1250A, 25KA Outdoor		Set	2			
		Total			25516	0	0	0

Name of the Supplier

Registration No.

Signature with Seal